


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 20 Twp. 24S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
330' FNL, 600' FEL, NW/4

Lease Owner F. G. Holl
Lease Name J. H. Cross #1-20 Well No. 1
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 18, 1980 19
Application for plugging filed June 18, 1980 19
Application for plugging approved June 18, 1980 19
Plugging commenced 6:00 PM June 18, 1980 19
Plugging completed 8:00 PM June 18, 1980 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4550'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 600' with 50 sacks 50/50 Pozmix at 600'
through open ended drill pipe; heavy mud to 270' with 6-26-80
40 sacks 50/50 Pozmis through open ended drill pipe;
heavy mud, Bridge and Plug at 40' with 10 sacks 50/50 Pozmix.
Pozmix. 5 sacks in rathole.

JUN 26 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Charles M. Hall (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
P. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 80.



[Signature]
Charles M. Hall, Notary Public.

My commission expires _____

15-047-20693-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - J. H. CROSS #1-20
Located: 330' FNL, 600' FEL, NW/4, Section 20-24S-17W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 11, 1980
COMPLETED: June 18, 1980

TOTAL DEPTH: 4550'

LOG

CASING RECORD

0 - 279	Surface Soil and Sand
279 - 1173	Shale, Sand, Red Beds
1173 - 1188	Anhydrite
1188 - 1825	Shale
1825 - 2170	Shale and Shells
2170 - 3100	Shale and Lime
3100 - 3340	Lime
3340 - 3800	Lime and Shale
3800 - 3941	Lime
3941 - 4068	Lime and Shale
4068 - 4228	Lime
4228 - 4392	Lime and Shale
4392 - 4428	Chert - Sand
4428 - 4474	Chert
4474 - 4505	Lime and Shale
4505 - 4550	Lime

Ran 6 joints used 8 5/8", 28# casing.
264.24' set at 276' K.B. Cemented
with 225 sacks 60/40 Pozmix with 3%
cc. Plug down at 2:00 PM, 6-11-80,
by Howco.

6-26-80

RECEIVED
REGISTRATION COMMISSION

JUN 26 1980

CONSERVATION DIVISION
Wichita, Kansas

Plugged.

Deviation Surveys: 1° at 2170'
1° at 4428'