

STATE OF KANSAS
STATE CORPORATION COMMISSION
207 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,304 - 0000

LEASE NAME McIntyre

WELL NUMBER _____

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 24 TWP. 24S RGE 17 XX or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced Oct. 4, 1994

Plugging Completed Oct. 7, 1994

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR WHITE & ELLIS DRILLING INC.

ADDRESS P O BOX 48848 Wichita, Ks. 67202

PHONE# (316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Oct. 6, 1994 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well-log attached? _____

Producing Formation _____ Depth to Top PBTD ~~XXXXXX~~ 4353 T.D. 4400

Show depth and thickness of all water, oil and gas formations. Perfs: 4312-22.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	307	8 5/8	307	0
		0	4390	4 1/2	4390	2271'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Rigged up, pulled rods & tubing out of well. Pumped 90 gal. of sand, top of sand at 4250'

Pumped 4 sx. cement, shot off 4 1/2 at 2271. Top hole plug: 300# hulls, 15 sx. gel, 50 sx

cement, 10 sx. gel-100# hulls, blew hole in surface pipe at 300#. Ran 34 jts. tubing to

1030', pumped 175 sx circulated cement. Pulled tubing, topped off with 30 sx. cement.

60-40- poz, 8% gel. (If additional description is necessary, use BACK of this form.)

SEE BACK.

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 Pratt, Kansas 67124

RECEIVED
STATE CORPORATION COMMISSION


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WHITE & ELLIS DRILLING INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

(Employee of ~~XXXXXX~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Judy Berry

(Address) PWS, INC.

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 94

Dorothy M. Furgason
Notary Public

My Commission Expires: February 6, 1997

TOP OF CEMENT DOWN 125 FT. FROM SURFACE, DUMPED 1.5 YARDS OF REDI MIX ON 10-14-94.