


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Edwards County. Sec. 27 Twp. 24 Rge. 17 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C/NE/SW  
Lease Owner Petroleum Energy, Inc.  
Lease Name MILLER Well No. 1  
Office Address Suite 710 - One Twenty Bldg., Wichita, KS 67  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed May 4 19 77  
Application for plugging approved 19  
Plugging commenced May 24 19 77  
Plugging completed May 31 19 77  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jasper H. Metz  
Producing formation Depth to top Bottom Total Depth of Well 4460'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	292'	none
				4 1/2"	4459'	2,222.07'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Dumped sand to 4350' and 4 sacks cement.

Shot pipe at 3950', 3700', 3600', 3500' and 2230'.

Pulled a total of 71 joints of 4 1/2" casing.

Sun Cementing squeezed well with 4 sacks hulls, 15 sacks gel and  
100 sacks cement with 2% added gel.

6-3-77

RECEIVED  
STATE CORPORATION COMMISSION

JUN 03 1977

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.  
P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.



(Signature)

Box 698, Great Bend, Kansas 67530

(Address)

Subscribed and sworn to before me this 2nd day of June 19 77

My commission expires May 21, 1980

Marla K. Haslam

Notary Public.

15-047-20224-0000  
 Per *coll* 4-28-77 from  
 Lou *Clinton*

STERLING DRILLING COMPANY  
 P. O. Box 129  
 Sterling, Kansas 67579

APR 29 1977

WELL LOG ----- MILLER #1  
 Located: C NE SW, Section 27-24S-17W, Edwards County,  
 Kansas.

OWNER: B and W Drilling Company  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 16, 1976  
 COMPLETED: October 24, 1976

TOTAL DEPTH: 4460'

<u>LOG</u>	<u>CASING RECORD</u>	
0 - 165 Sand - Clay	Ran 7 joints used 8 5/8" casing, 280.88' set at 292' K.B. with 225 sacks 60/40 Pozmis with 3% cc. Plug down at 11:00 PM, 10-16-76 by Allied Cement.	
165 - 1155 Shale, Sand, Red Bed		
1155 - 1169 Anhydrite		
1169 - 1180 Shale		
1180 - 2050 Shale and Lime Stgrs.		
2050 - 3445 Lime and Shale		
3445 - 3690 Lime, Shale and Chalk		
3690 - 4045 Lime and Shale		
4045 - 4315 Lime		
4315 - 4402 Lime, Chert and Sand		
4402 - 4420 Shale, Lime and Sand		
4420 - 4460 Sand, Chert, Lime		Ran 139 joints new 10.5#, 4 1/2" casing, 4452.68' set at 4459' K.B. with 100 sacks salt saturated Common Cement. Plug down at 6:00 AM, 10-24-76, by Allied.

WICHITA, KANSAS  
 CONSERVATION DIVISION  
 MAY 05 1977  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 5-5-77

*5-2-77*  
*[Signature]*