

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

EDWARDS County, Sec. 35 Twp. 24S Rge. (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Chief, Bankoff & Sunray Mid-Continent Oil Co.  
Lease Name Hawley Well No. 1  
Office Address P. O. Box 97 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 18 1958  
Application for plugging filed November 18 1958  
Application for plugging approved 19  
Plugging commenced November 18 1958  
Plugging completed November 18 1958  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug with 1/3 hulls, 20 sacks cement @240'  
Set second plug with 1/3 hulls, 10 sacks cement @35'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
Chief Drilling Co., Inc. - Box 97 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1958

My commission expires November 21, 1959

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public  
11-21-58  
NOV 21 1958  
PLUGGING COMMISSION  
FILE SEC 35 T 24 R 17 W  
BOOK PAGE 146 LINE 45  
CONSERVATION DIVISION  
Wichita, Kansas

15-047-00013-0000

WELL LOG

No. 1 Hawley

Chief Drilling Co., Inc.,  
Bankoff Oil Company and  
Sunray-Mid-Continent Oil Co.  
P. O. Box 97  
Great Bend, Kansas

Elevation: 2131' DF  
2129' GL  
2134' KB

Commenced: November 3, 1958  
Completed: November 18, 1958

No. 1 Hawley  
SW SW SW  
Section 35-24S-17W  
Edwards County, Kansas

Contractor: Chief Drilling Co., Inc.

Rotary: 0 - 4512' T.D.

DRY AND ABANDONED

Casing Record: 300' of 8-5/8" 28# surface casing with 200 sacks Pozmix cement and 2 sacks Calcium Chloride. Cement Circulated.

Figures Indicate Bottoms of Formations

Shale and Shells	0	410
Red Bed, Shale and Shells	410	500
Sand and Shale	500	650
Shale, Shells and Red Bed	650	1030
Shale and Shells	1030	1164
Anhydrite	1164	1177
Shale and Shells	1177	2025
Shale and Lime Streaks	2025	2140
Shale and Lime	2140	2425
Lime	2425	2530
Lime and Shale	2530	3495
Lime	3495	4242
Lime and Shale	4242	4391
Shale	4391	4402
Shale and Sand	4402	4409
Chert	4409	4442
Chert and Shale	4442	4452
Shale	4452	4457
Sand	4457	4478
Shale	4478	4493
Chert and Lime	4493	4512 T.D.

State of Kansas )  
County of Barton )

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SW SW SW of Section 35-24S-17W, Edwards County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover  
V. Richard Hoover, President

Subscribed and sworn to before me this 19th day of November, 1958.

11-21-58

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1958

Mary D. Johnson  
Notary Public

My Commission Expires:  
November 21, 1959

PLUGGING  
FILE SEC 35 T 24 R 17 W  
BOOK PAGE 448 LINE 45

CONSERVATION DIVISION  
Wichita, Kansas