

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20,871-

LEASE NAME Hawley "C" #2-35 <sup>0000</sup>

WELL NUMBER \_\_\_\_\_

SPOT LOCATION 440'FWL, 440'FSL SW/4

SEC. 35 TWP. 24 SRGE. 17 <sup>(S)</sup> or <sup>(W)</sup>

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/26/85

Plugging Completed 10/28/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4555'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	287'	none
				4 1/2"	4550'	2276'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged bottom with sand to 4350' & 4 sacks cement. Shot pipe at 3207', 3012', 2826', 2609', 2413', & 2276'. Pulled 55 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 6% gel.  
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1985

My Commission expires:



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

OCT 31 1985 10-31-85

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 01-84

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - HAWLEY "C" 2-35  
Located: 440' FSL; 440' FWL, SW/4, Section 35-24S-17W,  
Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 21, 1981  
COMPLETED: May 30, 1981

TOTAL DEPTH: 4555'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 108 Sand and Surface	Ran 7 joints new 8 5/8", 24# casing. 274.82' pipe set at 287' K.B. Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 2:15 PM, 5-21-81, by Howco.
108 - 290 Shale and Sand Strs.	
290 - 319 Shales	
319 - 1175 Red Bed, Sand	
1175 - 1186 Anhydrite	
1186 - 1515 Shale	
1515 - 2163 Shale and Lime Strs.	
2163 - 4555 Lime and Shale	Ran 110 joints new 4 1/2", 10.5# casing. 7 joints have been sand blasted. 4541.20' pipe set at 4550' K.B. Cemented with 225 sacks Regular mix. Plug down at 10:30 PM, 5-30-81, by Howco.

Deviation Surveys: 1° at 2163'  
1° at 4555'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1985 6-18-85

CONSERVATION DIVISION  
Wichita, Kansas