

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-21061-0000
API NUMBER

LEASE NAME White

WELL NUMBER 2-1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 1 TWP. 24 RGE. 18W (SE or W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 8-15-90

Plugging Completed 10-10-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G.Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(816) 995-3171 OPERATORS LICENSE NO. Gas

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	265'	none
				4 1/2"	4567'	2824'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 100# hulls and 50 sacks cement to 3600' Shot pipe
@2824'. Plugged with 300# hulls, 10 gel, 50 cement, 10 gel,
100# hulls, 125 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No.

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company **10-18-90**

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 17 day of Oct., 19 90

Jane Herzberg
Notary Public

My Commission Expires:



15-047-21061-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- WHITE #2-1

Located: 330' FNL, 1320' FWL, NW/4, Section 1-24S-18W,
Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 1, 1982

COMPLETED: August 8, 1982

TOTAL DEPTH: 4575'

LOG

0 - 100 Surface Soil and Sand
 100 - 268 Shale
 268 - 494 Shale and Sand
 494 - 1174 Shale, Sand and Red Beds
 1174 - 1194 Anhydrite
 1194 - 1535 Shales
 1535 - 2220 Shale - Lime Stringers
 2220 - 4575 Lime and Shale

CASING RECORD

Ran 6 joints new 24#, 8 5/8" casing.
 252.51' casing set at 265' K.B.
 Cemented with 210 sacks 60/40 Pozmix
 with 3% cc. Plug down at 11:45 AM,
 8-1-82, by Howco.

Ran 12 joints used 4 1/2", 10.5#
 casing and 103 joints new 4 1/2",
 10.5# casing. 4557.64' pipe set
 at 4567' K.B. Cemented with 100
 sacks Lite, 125 sacks 50/50 Pozmix
 plus regular additives. Plug down
 at 1:00 PM, 8-8-82, by Howco.
 Plugged rat hole with 10 sacks and
 plugged water well with 5 sacks.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 29 1990

CONSERVATION DIVISION
 Wichita, Kansas

Deviation Surveys: 1/2° at 2278'
 1° at 4098'