


Give All Information Completely  
Make Required Affidavit  
Make or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Edwards County. Sec. 10 Twp. 24 Rge. 18W (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner Twin Oil Company  
Lease Name Bogerd Well No. 1  
Office Address Dallas, Texas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 25- 1954 19  
Application for plugging filed July 25- 1954 19  
Application for plugging approved July 25- 1954 19  
Plugging commenced July 25- 1954 19  
Plugging completed July 25- 1954 19  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives, Pratt, Kansas.  
Producing formation Depth to top Bottom Total Depth of Well 4840 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand, redrock & clay	None	0	315'	8 5/8"	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy mud to 295 ft. 1 1/2 gallon of hulls in a large sack was forced ahead of permanent plug to 295' and cemented there with 20m sacks of cement. permanent plug and hulls was placed at 35' and cemented with 10 sacks of hulls to surface.

7-30-54

(If additional description is necessary, use BACK of this sheet).  
Name of Plugging Contractor Adkins Drilling Company, Inc.  
Address Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.  
Jim Adkins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jim Adkins*  
1502- 12th Great Bend, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July 19 54.  
*Pauline B. Adkins*  
Notary Public.

My commission expires 2-29-1956

23-8390-s - 6-51-20M  
PLUGGING  
FILE SEC 10 724 R SW  
BOOK PAGE 51 LINE 32

DRILLERS LOG

Elev. 2132 D. F.

Lease Owner & Operator      Twin Oil Company, Dallas, Texas  
 Contractor      Adkins Drilling Company, Inc. Great Bend, Kansas.  
 Lease—      Bogard No. 1      Ne. NE NE<sub>4</sub> of Sec. 10-24S-18W. Edwards County, Kansas.

Formation	From	To	Formation	From	To
Surface Sand & Clay	0	110			
Sand & Red Bed	110	315			

Set 300' of 8 5/8" surface casing  
 at 300' and cemented with 150 sacks  
 of cement and 200 # Ca. Cl.

Plug	300	301
Cement and open hole	301	315
Red Bed	315	581
Red Bed and Anhydrite	581	1319
Red Bed & Shale	1319	1755
Shale & Shells	1755	1965
Shale	1965	2100
Shale & Lime	2100	2434
Lime & Shale	2434	2800
Lime	2800	2895
Lime & Shale	2895	3906
Lime	3906	4400
Lime & Shale	4400	4445
Shale & Broken Sand	4445	4470
Lime	4470	4478
Shale & Sand	4478	4502
Lime	4502	4757
Shale & Sand	4757	4780
Lime	4780	4840

T. D. 4840'

Dry and Abandoned.

STATE OF KANSAS )  
 COUNTY OF BARTON )

7-30-54

I, JIM ADKINS, President of Adkins Drilling Co. Inc. do solemnly swear that the foregoing is a true and correct copy of the Drillers Log, to the best of my knowledge.

RECEIVED  
 STATE CORP.

*Jim Adkins*

Subscribed and sworn to before me this 26th day of July 1954.

*Paul B. Adkins*  
 Notary Public.

My Commission expires 2-29-1956.

PLUGGING  
 SEC 10 T 24 R 18W  
 DECK PAGE 21 LINE 32