

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,246 -  
LEASE NAME Slentz 0000  
WELL NUMBER 1-11  
SPOT LOCATION C SE/4 NE/4 SW/4  
SEC. 11 TWP 24S RGE. 18 (~~25S~~ W)  
COUNTY Edwards  
Date Well Completed 3-22-85  
4:00 AM,  
Plugging Commenced 3-22-85  
6:30 AM,  
Plugging Completed 3-22-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rine Exploration Company  
ADDRESS Suite 645, 300 West Douglas  
Wichita, Kansas 67202

PHONE # 816 ) 262-5418 OPERATORS LICENSE NO. 5020

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	395'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud, 50 sacks at 1200'; 80 sacks at 510';  
Bridge, plug and 10 sacks at 40'; 15 sacks in rathole; 10 sacks in mousehole.  
Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
Address P. O. Box 129  
Sterling, Kansas 67579

4-12-85

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
APR 12 1985

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
(Address) P. O. Box 129  
Sterling, Kansas 67579



SUBSCRIBED AND SWORN TO before me this 25 day of March, 1985.

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

WELL LOG - - - - - SLENTZ #1-11

SE NE SW, Sec. 11-24S-18W  
Edwards County, Ks.

OWNER Rine Exploration Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company  
COMMENCED: March 15, 1985  
COMPLETED; March 22, 1985

TOTAL DEPTH: 4595'

LOG

0 - 60	Clay and Gravel
60 - 395	Sand & Shale
395 - 595	Redbed & Shale
595 - 1202	Shale
1202 - 1220	Anhydrite
1220 - 1910	Shale
1910 - 4595	Lime & Shale

CASING RECORD

Ran 9 joints 23# 8 5/8" OD casing  
Tallied 379.81' set at 395' KB.  
Cemented with 275 sacks Class A, 2%  
Gel, 3% cc. Cement circulated.  
Plug down at 7:45 3-15-85 by  
Bouie

Plugged

DEVIATION SURVEYS

2° at 2252'  
1° at 4442'  
1½° at 4595'

4-12-85

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1985

CONSERVATION DIVISION  
Wichita, Kansas