


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 18 Twp. 24S Rge. 20W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Imperial Oil Company
Lease Name WESTPHAL Well No. 1
Office Address 780 Fourth National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-12-64 19__
Application for plugging filed 2-12-64 19__
Application for plugging approved 2-12-64 19__
Plugging commenced 2-12-64 19__
Plugging completed 2-12-64 19__
Reason for abandonment of well or producing formation No commercial quantities of oil found.
If a producing well is abandoned, date of last production - - - 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elbing
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4699 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing			8-5/8"	244'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 600 ft. with 25 sacks cement;
set second plug at 240 ft. with 20 sacks cement;
set top plug at 40 ft. with 10 sacks cement.

3-4-64

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address Box 97, WaKeeney, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Raymond R. Dombaugh (employee of owner) or (~~owner or lessee~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Raymond R. Dombaugh (Raymond R. Dombaugh)

780 Fourth National Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 64

My commission expires July 5, 1966

Bette J. Silcott
Bette J. Silcott Notary Public.

15-047-00273-0000

DRILLER'S LOG

Imperial Oil Company
 Fourth National Bank Bldg.
 Wichita, Kansas

WESTPHAL NO. 1
 C SW SE, Sec.18-24S-20W
 Edwards County, Kansas

Elevation: 2280 KB
Total Depth: 4699 ft.
Commenced: 1-30-64
Completed: 2-12-64
Contractor: Imperial Oil of Kansas, Inc.
Casing Record: Set 8-5/8" at 242' with 200 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 3-4-64
 MAR 4 1964

CONSERVATION DIVISION
 Wichita, Kansas

Figures indicate bottom of formations:

		<u>TOPS</u>
Surface	242'	Stone Corral Anhydrite 1411 (f 869)
Shale & Shells	326'	Base Stone Corral 1440 (f 840)
Sand & Shale	794'	Heebner 3972 (-1692)
False Anhydrite	807'	Toronto 3991 (-1711)
Dakota Sand	1000'	Lansing 4081 (-1801)
Sand & Shale	1411'	Marmaton 4456 (-2176)
Anhydrite	1440'	Cherokee Shale 4590 (-2310)
Shale	1525'	Mississippian (Osage) 4670 (-2390)
Shale & Red Bed	1765'	
Shale & Shells	2165'	Rotary Total Depth 4699 (-2419)
Shale & Lime	4681'	
Lime & Chert	4699'	

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

Raymond R. Dombaugh
 Raymond R. Dombaugh

Subscribed and sworn to before me this 27th day of February, 1964.

My commission expires: July 5, 1966

Bette J. Silcott
 Bette J. Silcott, Notary Public