

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-069-20147 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Energy Exploration & Prod. Inc.

Complete Address Suite 6001012 Baltimore St. Kansas City Mo. 64105

Lease Name Arsib Well No. 1

Location C-5E-5E Sec. 26 Twp. 24 Rge. 30 (East)(West)

County Gray Total Depth 5118'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Lakin Drilling Co.

Address Box 69 Lakin, Kansas 67860 License No. _____

Operation Completed: Hour: 4:30 AM Day: 9 Month: January Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 477' of 8 1/2" surface casing cement circulated
with 300 Sbx of cement with 3% CB. 1st plug at 1450'
with 70 Sbx of cement. 2nd plug at 460' with 40 Sbx of
cement. 3rd plug 40' to 0' with 10 Sbx of cement.
They pumped 5 Sbx of cement in rat hole. The
plugging was accomplished by Halliburton Co.
They used 50/50 pause cement with 2% Jell.

RECEIVED
STATE CORPORATION COMMISSION

1-19-82

JAN 19 1982

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Tuls
Conservation Division Agent
Wichita, Kansas

DATE 2-5-82
INV. NO. 9241-W

166.34

STATE OF TEXAS
COUNTY OF DALLAS

NOTARY PUBLIC

My Comm. Expires

26