

J
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name National Associated Petroleum Company

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name Minnie C. Malin Well No. # 1

Location C NW NE Sec. 27 Twp. 24 Rge. 17 (E) (W) W

County Edwards Total Depth 4405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Aspen Drilling Company

Address: Box 783, Great Bend, Kansas License No. _____

Operation Completed: Hour 3:30 PM Day 25th Month June Year 1965

The Above well was plugged as follows:

259' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 220'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 250', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ashie Elving
Well Plugging Supervisor

DATE 6/28/65

INV. NO. 1371-4