

*W*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
5-19-64  
MAY 19 1964

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Western Petroleum Co., Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name Bogerd Well No. # 1

Location NE NE NE Sec. 10 Twp. 24 Rge. 18 (E) W

County Edwards Total Depth 4840

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Western Petroleum Co., Inc.

Address: 925 Patton Road, Great Bend, Kansas License No.

Operation Completed: Hour 3:00AM Day 18th Month May Year 1964

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cement circulated. Fluid level was up in  
the hole. 1st cementing plug and 1 sack hulls was pushed to 275', and  
cemented with 25 sacks, through the drill pipe. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged solid with hulls,  
and cemented with 10 sacks to base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/19/64  
INV. NO. 9168-w

Signed: Archie Elving  
Well Plugging Supervisor