

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-21,035-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720, 4th Financial Center, Wichita, Kansas 67202

Lease Name Wheaton Well No. 1-20

Location 100'N-C-E/2-SE Sec. 20 Twp 24 Rge. 18 (East)(West)

County Edwards Total Depth 4590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Co. Inc.

Address Box 448 Eldorado Kansas 67042 License No. _____

Operation Completed: Hour: 1:45 P.M. Day: 2 Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1000'. 1st plug at 960' with 65 bbls of cement. 2nd plug at 620' with 45 bbls of cement. 3rd plug on solid bridge at 40' to 0' with 10 bbls of cement. Then they circulated 10 bbls of cement in rat hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Sun Cementing. They put 5 bbls of cement in water well.

Amount of Surface Casing: 593' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
5-8-82

MAY - 8 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 5-28-82
INV. NO. 244-W

149.18