

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-04720977-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720 fourth Financial Center Wichita Kansas 67202

Lease Name Cross Well No. 1-20

Location C-NW-NW Sec. 20 Twp. 24 Rge. 18N (East)(West)

County Edwards Total Depth 4640'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Co.

Address _____ License No. _____

Operation Completed: Hour: 11:45 PM Day: 19 Month: December Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 596' of 8 5/8" surface casing cement circulated with 200 lbs of
light & 125 lbs of common cement with 3% Jell & 3% C.C. The anhydrate
is at 617' to 627'. 1st plug at ⁶³⁰ 630' with 85 lbs of cement
2nd plug ~~pushed~~ rubber plug to 570' with 35 lbs of cement.
3rd plug 40' to 0' on solid bridge with 10 lbs of cement. Then
pumped 5 lbs of cement in rat hole & 2 lbs cement in
water well. Plugging accomplished by Sun
Cementing out of Great Bend. The cement used was common
with 2% Jell & 3% C.C.

12-22-81

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Little
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1981
CONSERVATION DIVISION
Wichita Kansas