

*W* KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
*11-16-64*  
NOV 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Moran Well No. # 1

Location C SW SW Sec. 23 Twp. 24 Rge. 20 (E)    (W) W

County Edwards Total Depth 4700

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.   

Operation Completed: Hour 3:00PM Day 13th Month Nov. Year 1964

The Above well was plugged as follows:

283' of 8 5/8" surface pipe, cemented with 225 sacks, circulated.

Fluid level in the hole was full. 1st cementing plug and 1/4 sack of  
hulls was pushed in fluid to 275', and cemented with 35 sacks, through  
the drill pipe. Fluid level in the hole was now at 50'. 2nd cementing  
plug, bridged with hulls on fluid at 50', and cemented with 15 sacks,  
to the base of the cellar. Rat and mouse hole bridged and cemented  
with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/16/64

NO. 173-w