

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20384-0000 ✓

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name F.G. Holl

Complete Address 6427 E. Kellogg Wichita, KS 67207

Lease Name Wolfe Well No. 1-11

Location NW NW NE Sec. 11 Twp. 24 Rge. 18W (East) (West)

County Edwards Total Depth 4570'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour: 10:00AM Day: 1 Month: 9 Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

258' of 8 5/8" SP W/250 sks

4 1/2' csg. set @ 4569' W/150 sks

PB to 4450' Perfs 4412' to 4416' SB to 4350' & 4 sks

Pump 15 gel 6 hulls 10 gel, release plug and displace W/125 sks

50/50 pozmix 4% gel 3% C.C.

Cemented by Allied Recovered 2425' of 4 1/2" csg. SIP 200#

9-4-81

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agents

INVOICED

DATE 10/6/81

INV NO. 7809-W