

15-047-00284-0000

Form CP-3  
Rev. 6-26-62

Ye  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 6 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Co.

Complete Address: P. O. Box 521, Tulsa, Oklahoma

Lease Name Kindsvater Well No. # 1

Location C NE NW Sec. 28 Twp. 24 Rge. 19 (E) (W) W

County Edwards Total Depth 4619

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 2nd Month May Year 1963

The Above well was plugged as follows:

295' fo 8 5/8" surface pipe, cement circulated with 200 sacks. 4619' of  
4 1/2" long string, cemented with 150 sacks. Perferation 4558' to 70'.  
Sanded to 4540', cemented with 3 sacks. Fluid in hole was to the top of  
surface pipe. Fluid would not bail down in hole. Plug was pushed down to  
200', 10' rock bridge and cemented with 3 sacks, let set over night, Next  
morning fluid would not bail down in hole. 7 sacks cement and 30# calcium  
chloride was mixed and put through dump bailer on plug and let set for  
3 hours. Fluid in hole bailed down O.K., 10 more sacks cement was set on  
plug. Hole was filled to 40' with mud. 10' rock bridge, 10 sacks cement  
to base cellar. 2713' of 4 1/2" long string recovered from hole.  
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 5/6/63

INV. NO. 4019-W