

15-047-20932-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

RECEIVED FORM CP-1  
KANSAS CORPORATION COMMISSION  
1-25-95  
JAN 25 1995

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 047-20932 SWD D-23.452 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)

ADDRESS 6427 E Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE CROSS WELL# 4-24 SEC. 24 T. 24 R. 18W (East/West)

70'S & 230'E of SW- NW -NE SPOT LOCATION/QQQQ COUNTY Edwards

4220' FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

2080' FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# D-23.452

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 265' CEMENTED WITH 210 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 1023' CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 554 to 570

ELEVATION 2146KB T.D. 4600' PBD 979' ANHYDRITE DEPTH 1132 (+1014)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, Ks. 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893  
(company name) (contractor's)

ADDRESS P.O. Box 847 Pratt, Ks. 67124 PHONE # ( ) (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/25/95 AUTHORIZED OPERATOR/AGENT: Elmer H. Hazel  
(signature)

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

JAN 25 1995

CONSERVATION DIVISION  
WICHITA, KS

WELL LOG - - - - - CROSS #4-24  
Located: 990' FNL; ~~660'~~<sup>560'</sup> FWL, NE/4, Section 24-24S-18W,  
1060' Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 15, 1981  
COMPLETED: September 21, 1981

TOTAL DEPTH: 4600'

TO S E 230' E of  
SW NW NE

<u>LOG</u>	<u>CASING RECORD</u>
0 - 268 Shale	Ran 6 joints new 8 5/8", 24# casing.
268 - 675 Shale, Sand, Red Bed	252.99; set at 265' K.B. Cemented
675 - 1186 Shale	with 210 sacks 60/40 Pozmix with 3% cc.
1186 - 1202 Anhydrite	plug down at 6:45 PM, 9-15-81, by Howco.
1202 - 1760 Shale	
1760 - 2252 Shales and Lime Str.	
2252 - 4575 Lime and Shale	
4575 - 4600 Lime	Plugged.

Deviation Surveys: 3/4° at 2252'  
1 3/4° at 4480'



## Kansas Corporation Commission

Bill Graves, Governor   Susan M. Seltsam, Chair   F.S. Jack Alexander, Commissioner   Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director   Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 26, 1995

F G Holl Company L L C  
6427 E Kellogg P O Box 780167  
Wichita KS 67278-0167

Cross #4-24  
API 15-047-20,932  
4220 FSL 2080 FEL  
Sec. 24-24S-18W  
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

David P. Williams  
Production Supervisor


District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760

App SYR NW, NE

F.G. HOLL  
6427 E. KELLOGG #4-24 CROSS 'OWWO'  
WICHITA, KS 67207  
CONTR STERLING DRILLING CO. CTY EDWARDS

24-24-18W  
1060'FNL&  
2080'FEL, NE/4

GEOL \_\_\_\_\_ FIELD WAC



ELV 2146 KB SPD 8/24/83 CARD ISSUED 12/8/83 IP SWDW

CEC HILLS 554-570  
G. LAINE GYPSUM??

API 15-047-20,932-A

LOG	Tops	Depth/Datum
HEEB		3408-1262
BR LM		3928-1782
LANS		3937-1791
BKC		4247-2101
CHER SH		4378-2232
CHER SD		4445-2299
KIND SH		4536-2390
KIND SD		4560-2414
VIOLA		4575-2429
RTD&LTD		4600-2454

OLD INFO: OPERATOR WAS F.G. HOLL, #4-24 CROSS, SPD 9/15/81, SET 8 5/8 " 265/200 SX, COMP. AS D & A / VIOLA, (CARD ISSUED 10/8/81), CONTR: STERLING DRILLING COMPANY  
DST (1) 4406-4430 (CHER) / 30-30-90-30, REC 210' MUD, SIP 34-177#, FP 27-27 / 33-140#  
DST (2) 4406-4480 (CHER) / 30-30-60-30, REC 90' DM, 260' MGW, SIP 1228-1099#, FP 89-122 / 186-244#  
NEW INFO: FR 8/8/83, RE-ENTERED E 8/24/83, WSH DWN, SET 4 1/2 " 1024; MICT - CO, PF (CED HILLS) 20/ 554-570, AC 1000G & 15 BS, SWB LD, SWDW - INJECTION RATE SATISFACTORY

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS