

15-083-10067-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER Comp'd 10-02-63 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR K & E Drilling, Inc. OPERATOR'S LICENSE NO. 5266 6/90

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Strecker "A" WELL NO. 2 WELL LOCATION NE NW COUNTY Hodgeman

SEC. 9 TWP. 24S RGE. 21 (E or W) TOTAL DEPTH 4730' PLUG BACK TD +4,690'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 205' CEMENTED WITH 200 SACKS

CASING SIZE 4-1/2" SET AT 4729' CEMENTED WITH 250 SACKS

PERFORATED AT 4650-54'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand to 4,600' and cap w/5 sxs cement. Shoot-off 4 1/2"

casing @1,000' plus and pull from well. Spot 50 sxs cement @1,000', 50 sxs @500', 40

sxs @280', 15 sxs at surface and cap.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?   
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Al Hammersmith PHONE # (316) 792-2729  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1990

ADDRESS P.O. Box 2050, Great Bend, KS 67530

PLUGGING CONTRACTOR Cheyenne Well Service LICENSE NO. 6454 6/90  
CONSERVATION DIVISION  
Wichita, Kansas

ADDRESS Ness City, KS 67560 PHONE # (913) 798-2282

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Wayne L. Brinegar Wayne L. Brinegar  
(Operator or Agent) Vice President

DATE: 1/12/90

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH MCCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

APR 18 1990

EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

January 18, 1990  
NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

K & E Drilling, Inc.  
100 S. Main, Suite 300  
Wichita, KS 67202

Strecker "A" 2  
Sec. 09-24-21W  
NE NW  
Hodgeman County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist Albrecht in cursive.

Shari Feist Albrecht  
Director

District: #1 304 W. McArtor  
Dodge City, KS 67202  
(316) 225-6760