

15-083-10069-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 10-18-63 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR K & E Drilling, Inc. OPERATOR'S LICENSE NO. 5266

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Strecker "A" WELL NO. 4 WELL LOCATION NW NW COUNTY Hodgeman

SEC. 9 TWP. 24S RGE. 21 (~~EXX~~(W) TOTAL DEPTH 4725' PLUG BACK TD 4530'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 206' CEMENTED WITH 200 SACKS

CASING SIZE 4-1/2" SET AT 4724' CEMENTED WITH 250 SACKS

PERFORATED AT 4434'-4440'; 4450'-4460'; (4676'-4679' below CIBP)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Inside of 4 1/2": sand to 4375' and spot cement plugs at

4375' (2 / sxs), 1470' (40 sxs), 720' (30 sxs), 240' (40 sxs) and 10 sxs @surface. Pump

100 sxs down 8-5/8" x 4 1/2" annulus.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Al Hammersmith PHONE # (316) 792-2729

ADDRESS P.O. Box 2050, Great Bend, KS 67530

X PLUGGING CONTRACTOR Cheyenne Well Service, Inc. X LICENSE NO. 6454

X ADDRESS P.O. Box 384, Ness City, KS 67560 X PHONE # (913) 798-2282

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Wayne L. Brinegar Wayne L. Brinegar
(Operator or Agent) Vice President

DATE: January 18, 1990

RECEIVED 1-24-90
STATE CORPORATION COMMISSION
JAN 24 1990
CONSERVATION DIVISION
Wichita, Kansas
RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1990
CONSERVATION DIVISION
Wichita, Kansas

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

APR 24 1990

EXPIRES

January 24, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

K & E Drilling, Inc.
100 S. Main, Suite 300
Wichita, KS 67202

Strecker "A" 4
NW NW
Sec. 09-24-21W
Hodgeman County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760