

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 24 TWP. 24S RGE. 18W NW
Location as in quarters or footage from lines:
440' FSL; 440' FEL, SE/4

Lease Owner F. G. Holl
Lease Name Cross #5-24 Well No. 5-24
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed June 2, 1982
Application for plugging filed June 2, 1982
Plugging commenced 1:00 PM, June 2, 1982
Plugging completed 3:30 PM, June 2, 1982
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie
Producing formation _____ Depth to top _____ bottom T.D. 4625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud thru openended drill pipe, 40 sacks
at 1080'; 50 sacks at 320'; bridge, plug
and 10 sacks at 40'; 10 sacks in rathole.
Used 50/50 Pozmix with 4% gel and 3% cc.

6-7-82
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
(Address)

P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 82.



[Signature]
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CROSS #5-24

Located: 440' FSL; 440' FEL, SE/4, Section 24-24S-18W,
Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 27, 1982

COMPLETED: June 2, 1982

TOTAL DEPTH: 4625'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing.
90 - 268 Shale	252.81' pipe set at 265' K.B.
268 - 797 Shale and Sand	Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 10:45 AM, 5-27-82, by Howco.
797 - 1191 Shale, Sand, Red Bed	
1191 - 1650 Shale, Lime Shells	
1650 - 2259 Lime Stringers - Shale	
2259 - 4625 Lime and Shale	Plugged.

Deviation Surveys: 1/4° at 2259'
1° at 4510'



**BULK MATERIALS DELIVERY 15-047-21042-0000
AND
TICKET CONTINUATION**

FOR INVOICE AND TICKET NO. 533158

DATE 6-2-82	CUSTOMER ORDER NO.	WELL NO. AND FARM Cross	COUNTY Edwards	STATE Ks.
CHARGE TO F. G. Holl		OWNER F. G. Holl	CONTRACTOR Sterling Drlg.	No. B 212400
MAILING ADDRESS		DELIVERED FROM Great Bend, Ks.	LOCATION CODE 50320	PREPARED BY S. C. Henry
CITY & STATE		DELIVERED TO Location	TRUCK NO. 4604-8206	RECEIVED BY <i>[Signature]</i>

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT	
		L	D		QTY.	MEAS.	QTY.	MEAS.			
				115 Pozmix Cement W/2% Gel							
504-043		1	B	Regular Portland	58	sk.			5.25	304.50	
506-105		1	B	Pozmix A	57	cu ft			2.46	140.22	
506-121		1	B	2 Halliburton Gel 2% allowed						NC	
507-277		1	B	2 Halliburton Gel 2% W/115	115				.37	42.55	
509-406		1	B	Calcium Chloride 3% W/115	3	sk			21.00	63.00	
THIS IS NOT AN INVOICE											
				Returned Mileage Charge	TOTAL WEIGHT	LOADED MILES	TON MILES				
				SERVICE CHARGE ON MATERIALS RETURNED			CU. FEET				
500-207		2	B	SERVICE CHARGE			CU. FEET 121		.95	114.95	
500-306		2	B	Mileage Charge	10,286	50	257.15		.70	180.01	
No. B 212400		CARRY FORWARD TO INVOICE					SUB-TOTAL				845.23