

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20,492-0000

LEASE NAME CROSS

WELL NUMBER 3-24

440' FNL  
SPOT LOCATION 1320' FEL NE/4

SEC. 24 TWP. 24 RGE. 18 ~~(E)~~ or (W)

COUNTY EDWARDS

Date Well Completed 6/18/79

Plugging Commenced 4/19/84

Plugging Completed 4/19/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg, Wichita, KS 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Steve Durrant State Plugger present

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation Cedar Hills Depth to top 605 bottom 717 T.D. 958

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

5-15-84

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	255.08'	none
				4 1/2"	969.19'	none

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged well with 60 sacks Regular Portland and 40 sacks of Pozmix A, 3 sacks Halliburton Gel 2% allowed; Calcium Chloride 3% w/100 from TD to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Suite 600, Colorado-Derby Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Klein

(Address) Suite 600 Colorado-Derby Bldg. Wichita, KS

SUBSCRIBED AND SWORN TO before me this 14 day of May, 19 84

ESTHER SIDENER  
NOTARY PUBLIC  
State of Kansas  
My Appointment Expires: 2/3/96

Esther Sidener  
Notary Public

My Commission expires: February 3, 1986

STERLING DRILLING COMPANY  
 P. O. Box 129  
 Sterling, Kansas 67579

WELL LOG ----- CROSS #3-24  
 Located: 440' FNL, 1320' FFL, NE/4, Section 24-245-18W,  
 Edwards County, Kansas

OWNER: F. G. Holl  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 20, 1979  
 COMPLETED: March 28, 1979

TOTAL DEPTH: 4595'

LOG

CASING RECORD

0 - 155 Sand and Clay  
 155 - 270 Clay and Shale  
 270 - 597 Shale, Sand and Red Bed.  
 597 - 688 Red Beds  
 688 - 1180 Shale  
 1180 - 1198 Anhydrite  
 1198 - 1525 Shale  
 1525 - 2085 Shale and Shells  
 2085 - 2197 Shale and Lime  
 2197 - 2325 Shale and Lime Strs.  
 2325 - 2610 Shale  
 2610 - 3570 Lime and Shale  
 3570 - 4058 Lime  
 4058 - 4450 Lime and Shale  
 4450 - 4465 Shale and Chert  
 4465 - 4595 Lime and Chert

Ran 6 joints used 28#, 8 5/8" casing,  
 255.08' set at 267' K.B. with 225  
 sacks 60/40 Pozmix with 3% cc. Plug  
 down at 8:15 PM, 3-20-79, by Howco.

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 15 1984

CONSERVATION DIVISION  
 Wichita, Kansas

Ran 23 joints new 10.5#, 4 1/2" casing,  
 969.19' set at 981' K.B. with 200 sacks  
 Howco Light, followed by 100 sacks  
 50/50 Pozmix. Plug down at 3:15 AM,  
 3-28-79, by Howco.