

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

C/E<sup>1</sup>/<sub>2</sub>/SW  
COUNTY Edwards SEC. 22 TWP. 24S RGE. 18 XE/W  
Location as in quarters or footage from lines:


Lease Owner Imperial Oil Co.  
Lease Name White Well No. 1-22  
Office Address 720 Fourth Financial Center-Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed 11-14-78  
Application for plugging filed Dec. 1983  
Plugging commenced 12-19-83  
Plugging completed 12-19-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Not economical to produce  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation Cherokee Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4506'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
		0	328'	8 5/8	328	0
		328'	4505	4 1/2		1746'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. 3 sx. hulls-10 gel-50sx. cement-10 gel-1 hull-  
8 5/8" wiper plug-100 sx. cement on top. 60/40 poz mix-2% gel-3% C.C.

Max. pressure-500#, Shut in pressure 300#--Job complete 11:00AM.  
PB TD 4460', top of perf. 4352-56'. Dumped 15 sx. sand to 4260', dumped 4 sx.  
cement to 4212', shot pipe at 1746'.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.  
Judy Berry (employee of owner) or (owner/operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry  
Box 847, Pratt, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1984

Charlene M. Dudley  
STATE CORPORATION COMMISSION Notary Public.

My Commission expires: 9/10/86

JAN 10 1984 1-10-84