

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

21W

Hodgeman County, Sec. 9 Twp. 24 Rge. ~~20~~ (E) (W) x

Location as "NE/CNW/SW" or footage from lines C of SW NW

Lease Owner Bovaird Supply Co.

Lease Name Strecker "A" Well No. #3

Office Address Box 897, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 4-25-66 19

Application for plugging approved 19


Plugging commenced 4-27-66 19

Plugging completed 5-12-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation Depth to top Bottom Total Depth of Well 4677' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4600', mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 12 sacks gel, followed with 40 sacks cement. Followed with 3 sacks gel and displaced with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1966

5-16-66

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer - Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of May, 1966

My commission expires 24 October 1968

Sidney D. Miller
Notary Public.

DRILLERS' LOG

Company:	James W. Hershberger
Contractor:	Jones-Gebert Oil, Inc.
Farm:	#3 Strecker "A"
	C SW NW, Sec. 9-24S-21W
	Hodgeman Co., Kansas
Commenced:	9/11/63
Completed:	9/21/63
Casing:	8-5/8" @234' w/200 sx.
	4-1/2" @4675' w/100 sx.

0	-	235	Shale
235	-	565	Redbed & blue shale
565	-	830	Redbed & shale
830	-	840	Elaine
840	-	920	Shale
920	-	1045	Sand
1045	-	1458	Shale
1458	-	1500	Anhydrite
1500	-	1710	Shale
1710	-	1965	Shale w/lime streaks
1965	-	2350	Shale
2350	-	2450	Lime & shale
2450	-	2635	Lime
2635	-	2805	Lime
2805	-	2945	Lime & shale streaks
2945	-	3160	Shale & lime
3160	-	3280	Lime
3280	-	3515	Shale & lime
3515	-	3660	Lime & shale
3660	-	3840	Shale & lime
3840	-	3845	Lime
3845	-	3980	Lime & shale
3980	-	4054	Lime
4054	-	4064	Lime & shale
4064	-	4160	Lime
4160	-	4195	Lime
4195	-	4280	Lime
4280	-	4359	Lime & some chert
4359	-	4425	Lime
4425	-	4500	Lime
4500	-	4562	Lime
4562	-	4635	Lime
4635	-	4677	Lime
		4677	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1966
CONSERVATION DIVISION
Wichita, Kansas

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #3 Strecker "A" C SW NW, Sec. 9-24S-21W, Hodgeman County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

George R. Jones
George R. Jones

State of Kansas, County of Sedgwick) ss:
Subscribed and sworn to before me, a Notary Public, in and for said County and State this 24th day of September, 1963.

My commission expires:
February 1, 1964

Barbara J. Layton
Barbara J. Layton, Notary Public