

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-083-10067-0000

API NUMBER None assigned

LEASE NAME Strecker "A"

WELL NUMBER 2

4,620 Ft. from S Section Line

3,300 Ft. from E Section Line

SEC. 9 TWP. 24S RGE. 21 (W)

COUNTY Hodgeman

Date Well Completed 10-02-63

Plugging Commenced 03-15-90

Plugging Completed 03-20-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

100 S. Main, Suite 300

ADDRESS Wichita, KS 67202

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 18, 1990 (date)

by Richard Lacey, District #1 (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Mississippian
Osage Depth to Top 4,650' Bottom 4,654' T.D. 4,730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	200'	None
				4-1/2"	4729'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor K & E Drilling, Inc. License No. 5266

Address 100 S. Main, Suite 300, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K & E Drilling, INC.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Brinegar Vice President

(Address) 100 S. Main, Suite 300, Wichita, KS 67202



AND SWORN TO before me this 2nd day of April, 19 90

Patricia A. Clarke
Notary Public


My Commission Expires: August 11, 1991

Spot 9 sxs sand to 4600'. Spot 10 sxs cement @4400'. Pulled tubing and shot 4-1/2" casing @1010'. Ran tubing to 987' and spotted 40 sxs cement. Pulled tubing to 500' and spotted 30 sxs cement. Had cement to surface. Pulled tubing out and pumped 85 sxs cement down 8-5/8" x 4-1/2" annulus and pressured to 200#. Put additional 10 sxs down casing and filled to surface. Ran wire-line and found cement 175' from surface. Shut-down 5 days. On 3-20-90 filled casing to surface with Redi-Mix, cut-off casing and capped well.

Plugging operations on 3-15-90 witnessed by KCC Representative, Richard Lacey and on 3-20-90 by KCC Representative Mike Wilson.

Cementing service by Halliburton Services (see Invoice #914253, attached).

15-083-10067-0000

ORIGINAL				REMIT TO:	
INVOICE		HALLIBURTON SERVICES		P.O. BOX 951046	
		A Halliburton Company		DALLAS, TX 75395-1046	
		INVOICE NO. 914253		DATE 03/15/1990	
WELL LEASE NO./PLANT NAME		WELL/PLANT LOCATION		STATE	WELL/PLANT OWNER
STRECKER A-2		HODGEMAN		KS	SAME
SERVICE LOCATION		CONTRACTOR		JOB PURPOSE	
GREAT BEND		CHEYENNE WELL SERV.		PLUG TO ABANDON	
ACCT. NO. 460690		CUSTOMER AGENT AL HAMMERSMITH		VENDOR NO.	
				CUSTOMER P.O. NUMBER	
				SHIPPED VIA COMPANY TRUCK	
				FILE NO. 92169	

K & E DRILLING, INC.
P. O. BOX 2050
GREAT BEND, KS 67530-2050

DIRECT CORRESPONDENCE TO:
SUITE 600
COLORADO DERBY BUILDING
WICHITA, KS 67202-0000

RECEIVED
MAR 26 1990

PRICE REF. NO.	DESCRIPTION	QUANTITY	U/M	UNIT PRICE	AMOUNT
PRICING AREA - MID CONTINENT					
000-117	MILEAGE	68	MI	2.20	149.60
		1	UNT		
090-910	MISCELLANEOUS PUMPING JOB	1	TRK	370.00	370.00
504-308	STANDARD CEMENT	105	SK	5.35	561.75
506-105	POZMIX A	70	SK	2.79	195.30
506-121	HALLIBURTON-GEL 2%	4	SK	.00	N/C
507-277	HALLIBURTON-GEL BENTONITE	8	SK	13.00	104.00
509-554	HALLIBURTON GEL	15	SK	6.95	104.25
510-222	BRADY FRAC SAND	9	SK	8.60	77.40
500-306	MILEAGE CMTG MAT DEL OR RETURN	170.48	TMI	.70	119.34
500-225	CEMENTING MATERIALS RETURNED	55	CFT	.32	17.60
500-207	BULK SERVICE CHARGE	230	CFT	.95	218.50
500-306	MILEAGE CMTG MAT DEL OR RETURN	794.48	TMI	.70	556.14
INVOICE SUBTOTAL					2,473.88
DISCOUNT-(BID)					371.06-
INVOICE BID AMOUNT					2,102.82
**KANSAS STATE SALES TAX					86.58
**BARTON COUNTY SALES TAX					20.37
INVOICE TOTAL PLEASE PAY THIS AMOUNT					\$2,209.77

OK

W

TERMS INVOICES PAYABLE NET BY THE 20TH OF THE FOLLOWING MONTH AFTER DATE OF INVOICE, UPON CUSTOMER'S DEFAULT IN PAYMENT OF CUSTOMER'S ACCOUNT BY THE LAST DAY OF THE MONTH FOLLOWING THE MONTH IN WHICH THE INVOICE IS DATED, CUSTOMER AGREES TO PAY INTEREST THEREON AFTER DEFAULT AT THE HIGHEST LAWFUL CONTRACT RATE APPLICABLE BUT NEVER TO EXCEED 18% PER ANNUM. IN THE EVENT IT BECOMES NECESSARY TO EMPLOY AN ATTORNEY TO ENFORCE COLLECTION OF SAID ACCOUNT, CUSTOMER AGREES TO PAY ALL COLLECTION COSTS AND ATTORNEY FEES IN THE AMOUNT OF 20% OF THE AMOUNT OF THE UNPAID ACCOUNT.

Rec 4-3-90

DRILLERS' LOG

OPERATOR: James W. Hershberger
 CONTRACTOR: Jones-Gebert Oil, Inc.
 FARM: #2 Strecker "A", C NE NW
 Sec. 9-24S-21W
 Hodgeman Co., Kansas
 COMMENCED: 9/22/63
 COMPLETED: 10/2/63
 CASING: 8-5/8" @230' w/200 sx.
 4-1/2" @4729

0	-	35	Soil & rock
35	-	205	Blue shale
205	-	600	Shale
600	-	820	Blue shale & red bed
820	-	830	Blaine
830	-	890	Shale
890	-	1025	Sand
1025	-	1443	Shale
1443	-	1460	Anhydrite
1460	-	1870	Shale & shells
1870	-	2240	Shale & shells
2240	-	2300	Shale & lime
2300	-	2530	Brown Lime
2530	-	2670	Lime
2670	-	2835	Lime
2835	-	2965	Lime & shale
2965	-	3125	Lime & shale
3125	-	3238	Lime & shale
3238	-	3450	Shale & lime
3450	-	3605	Lime & shale
3605	-	3720	Lime & shale
3720	-	3858	Lime & shale
3858	-	3920	Lime & shale
3920	-	4070	Lime & shale
4070	-	4130	Lime
4130	-	4215	Lime
4215	-	4280	Lime & chert
4280	-	4385	Lime
4385	-	4450	Lime
4450	-	4470	Lime
4470	-	4490	Lime
4490	-	4550	Lime
4550	-	4610	Lime
4610	-	4643	Lime
4643	-	4668	Lime & chert
4668	-	4678	Miss.
4678	-	4730	Cherty lime
		4730	Rotary Total Depth

I, Albert J. Gebert III, do hereby certify that the above and foregoing is a true and correct copy of the log of the #2 Strecker "A", C NE NW, Sec. 9-24S-21W, Hodgeman Co., Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

Albert J. Gebert III
 ALBERT J. GEBERT III

State of Kansas, County of Sedgwick) ss:
 Subscribed and sworn to before me, a Notary Public, in and for said
 County and State of October, 1963.

My Commission Expires: 3 1990
 February 1, 1964

4-3-90
 Barbara J. Layton, Notary Public

CONSERVATION DIVISION
 Wichita, Kansas