

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-083-10069-0000  
API NUMBER None assigned

LEASE NAME Strecker "A"

WELL NUMBER 4

4,620 Ft. from S Section Line

4,620 Ft. from E Section Line

SEC. 9 TWP. 24S RGE. 21 ~~XXX~~ (W)

COUNTY Hodgeman

Date Well Completed 10-18-63

Plugging Commenced 03-15-90

Plugging Completed 03-20-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

100 S. Main, Suite 300

ADDRESS Wichita, KS 67202

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 24, 1990 (date)

by Richard Lacey - District #1 (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Mississippian  
Osage Depth to Top 4434' Bottom 4460' T.D. 4725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	206'	None
				4-1/2"	4724'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor K & E Drilling, Inc. License No. 5266

Address 100 S. Main, Suite 300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K & E Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, as shown to me and  
Wayne L. Brinegar Vice President

RECEIVED  
STATE CORPORATION COMMISSION  
4-3-90

(Signature) Wayne L. Brinegar

(Address) 100 S. Main, Suite 300, Wichita, KS

67202

PATRICIA A. CLARKE  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 8-11-91

MAR 03 1990

CONSERVATION DIVISION  
Wichita, Kansas

AND SWORN TO before me this 2nd day of April, 19 90

Patricia A. Clarke  
Notary Public

My Commission Expires: August 11, 1991

Spot 14 sxs sand on bottom and capped with 10 sxs cmt. Set tubing @1470' and displaced w/91 sxs cement. Pulled tubing and filled casing w/35 sxs cmt. Pumped 40 sxs down 8-5/8"x4 1/2" annulus. Pressured to 300# and held. Ran measuring line down casing and found cement @320'; shut down 5 days. Filled casing with Redi-Mix cement to surface. Cut-off casing and capped well.

Plugging operations on 3-15-90 witnessed by KCC Representative, Richard Lacey and on 3-20-90 by KCC Representative Mike Wilson.

Cementing service by Halliburton Services (see Invoice #914147, attached).

15-083-10069-0000 COPY *Chw nw*


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- JAMES W. HERSHBERGER  
Farm- Strecker "A" No. 4

SEC. 9 T. 24 R. 21W  
C NW NW

Total Depth. 4725'  
Comm. 10-4-63 Comp. 10-18-63  
Shot or Treated.  
Contractor. Jones-Gebert Oil  
Issued. 2-1-64

County Hodgeman  
KANSAS



Elevation. 2369' RR

Production. 277 BOPD-NW

CASING:

8 5/8" 206' cem w/ 200 sx  
4 1/2" 4724' cme w/ 250 sx

Figures indicate Bottom of Formations.

surface	210
red bed	235
red & blue shales	830
Blaine Sand	850
shale & sand	1452
Anhydrite	1468
shale & shells	2145
shale & lime	2435
Brown lime	2595
lime	2940
lime & shale	4067
lime	4665
shale & lime	4676
Mississippi	4679
lime	4725 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite (SMP)	1452
Heebner	3961
Brown Lime	4052
Lansing	4062
Base Kansas City	4462
Marmaton	4434
Fort Scott	4588
Cherokee	4612
Mississippi	4664
Mississippi Osage	4674

U.S. LIBRARY

*1-24-90*

RECEIVED  
STATE COOPERATION COMMISSION

JAN 24 1990

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE COOPERATION COMMISSION

JAN 22 1990

CONSERVATION DIVISION  
Wichita, Kansas

