

15-083-00169-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 8 Twp. 24S Rge. 21W (E) (W)  
 Location as "NE/CNW/SW" or footage from lines: C NW NE  
 Lease Owner Mull Drilling Co. Inc.  
 Lease Name Schmidt Well No. 1  
 Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.  
 Date well completed 11-18-62 19.  
 Application for plugging filed 11-18-62 19.  
 Application for plugging approved 11-18-62 19.  
 Plugging commenced 11-18-62 19.  
 Plugging completed 11-18-62 19.  
 Reason for abandonment of well or producing formation Non productive.

If a producing well is abandoned, date of last production 19.  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Liberal, Kansas  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4750 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled to within 250' of surface, and a plug put at this depth with 1/2 sack hulls and 35 sacks cement. Hole filled to within 40' of surface and 15 sacks cement and a plug put at this depth. This completed plugging of hole. Two sacks cement was put in rat hole plugging same.

NOV 28 1962

*Rec'd 11-28-62*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. tools.  
 Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Joseph O. Butts*  
 Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1962

*Better H. Salter*

My commission expires October 16, 1965

Notary Public.



15-083-00169-0000

R O T A R Y D R I L L E R S L O G

COMPANY: Mull Drilling Co., Et al ROTARY DRILLING COMMENCED: 11-7-62  
Wichita, Kansas

CONTRACTOR: Mull Drilling Company, Inc. Rotary DRILLING COMPLETED: 11-19-62  
Wichita, Kansas

CASING RECORD: Set 271' of 8 5/8" casing w/175 sxs.cement. LOCATION: Schmidt #1  
C NW NE 8-24S-21W  
Hodgeman County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

330'	Gray Clay Shale
540'	Shale w/Shellis
1450'	Shale
1468'	Anyhydrite
1925'	Shale
2230'	Shale w/Lime
2210'	Shale
4096'	Lime w/Shale
4130'	Lime
4455'	Lime w/Shale
4485'	Lime
4615'	Lime w/Shale
4620'	Lime
4646'	Lime w/Shale
4680'	Cherty Lime & Shale
4695'	Cherty Lime
4750'	Mississippi and Total Depth

NOV 28 1962

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.



MULL DRILLING COMPANY, INC.

*Joseph E. Brangardt, Jr.*  
Joseph E. Brangardt, Jr.

} SS

COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 27th day of November, 1962.

*Lola L. Foster*  
Lola L. Foster, Notary Public

My commission expires April 17, 1966.