


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.,  
245 North Water  
Wichita, KS 67202

Hodgeman County, Sec. 5 Twp. 24S Rge. 21 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
150' SW of C  
Lease Owner Pendleton Land & Exploration, Inc.  
Lease Name V. Gleason Well No. #2  
Office Address 23 Inverness Way East, Englewood, Colo. 80112  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed 1-30-81 19  
Application for plugging filed 1-30-81 19  
Application for plugging approved 1-30-81 19  
Plugging commenced 1-30-81 19  
Plugging completed 1-30-81 19  
Reason for abandonment of well or producing formation

Commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.  
Producing formation Depth to top Bottom Total Depth of Well 4860'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	583'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug-set.

Plug @ 900' w/60 sx.

Plug @ 600' w/35 sx.

Plug @ 40' w/10 sx.

Rat Hole 5 sx.

2-9-81

FEB - 9 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buffalo Drilling Company, Inc.

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jerald W. Rains, President of Buffalo Drilling Company, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

*Jerald W. Rains*

435 Page Court, 220 W. Douglas, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of February, 19 81

*Juanita M. Green*

Juanita M. Green Notary Public.

My commission expires

10-4-83



DRILLER'S LOG

COMPANY: Pendleton Land & Exploration, Inc. SEC. 5 T. 24S R. 21W

WELL NAME: V. Gleason #2

LOC. 150' SW of C

COUNTY: Hodgeman

RIG NO. #7

TOTAL DEPTH 4860'

ELEVATION

COMMENCED: 1-18-81 COMPLETED: 1-30-81

CONTRACTOR: Buffalo Drilling Company, Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 583' w/300 sx. 50/50 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	225
Shale & Sand	515
Shale & Shells	1115
Shale & Clay	1445
Shale	1730
Shale & Lime	2320
Lime & Shale	2620
Shale & Lime	2998
Lime	3115
Lime & Shale	3350
Lime	3985
Lime & Shale	4133
Lime	4860
<u>ROTARY TOTAL DEPTH</u>	<u>4860</u>

2-9-81

CONSERVATION DIVISION

FEB - 9 1981

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)


SS:

I, Jerald W. Rains, President of Buffalo Drilling Company, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

V. Gleason #2 well.

Jerald W. Rains  
Jerald W. Rains



Subscribed and sworn to before me this 2 day of February, 1981.

Juanita M. Green  
Juanita M. Green