

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Hodgeman County, Sec. 5 Twp. 24S Rge. 21 (E)W (W)
Location as "NE/CNWxSWx" or footage from lines C N/2 NW NW
Lease Owner Pickrell Drlg. Co. ; Wichita, Kansas 67202
Lease Name Gleason "G" Well No. #1
Office Address 705 Fourth National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Nov. 3 1969
Application for plugging filed June 16 1970
Application for plugging approved June 16 1970
Plugging commenced June 26 1970
Plugging completed June 30 1970
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 23 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation Marmaton Depth to top 4406 Bottom 4584 Total Depth of Well 4665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260	None
				4 1/2	4650	2698

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

June 26, 1970 Plugged off bottom. Dumped sand to 4400'. Mixed and dumped 5 sx of cement to 4360'.

June 30, 1970 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing:
80 sx cement, 6% sx of gel
30 sx cement, 2 sx of gel
Released plug and 10 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. BOX 1082 GREAT BEND, KANSAS 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson

705 Fourth National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 15th day of July, 19 70



Esther Lamone
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 9/25/69
Rotary Drilling Completed 10/7/69

LOCATION: Gleason "C" No. 1, C N/2 NW NW, Sec. 5-24S-21W
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 13 Jts. 28# 8-5/8" Surface Casing set @ 260' KB. Cemented with 165 Sacks. Completed 8:30 P.M. Sept. 25, 1969. Circulated.

Ran 149 Jts. 5-1/2" 14# Casing @ 4656'. Cemented w/125 sacks 50-50 Pozmix 4% Gel followed by 60 sacks Common. Plug down 4:30 A.M. October 7, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Clay		<u>C.F.S.</u>
260	Clay Lime Shells		4010
500	Shale		4420
805	Shale & Red Bed		4440
830	Blaine		4455
905	Shale		4572
1035	Sand		4587
1390	Shale & Sand		4665
1425	Shale		
1460	Anhydrite		
2445	Shale & Lime		<u>S.L.M.</u>
2560	Lime & Shale		
2740	Shale & Lime	Board	4053.10
3020	Lime & Shale	Strap	4051.01
3810	Shale & Lime		2.09 Difference
4072	Lime & Shale		
4145	Shale & Lime		
4520	Lime & Shale		<u>Slope Tests</u>
4593	Ft. Scott		2000
4665	RTD		2500
			3000
			3500
			4000
			4500

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 22 15th day of October, 19 69, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L.M. Whiting Notary Public