


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 5 Twp 24S Rge. XX 21 (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner Pickrell Drilling Company
Lease Name Gleason "C" Well No. 2
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 5 19 70
Application for plugging filed February 5 19 70
Application for plugging approved February 5 19 70
Plugging commenced February 5 19 70
Plugging completed February 5 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation Depth to top Bottom Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 800' w/30 sacks cement, plug @ 260' w/30 sacks
top plug @ 45' w/15 sacks

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 10th day of February, 1970



Esther Lamone
Notary Public.

January 19, 1973

ROTARY DRILLING LOG

15-083-20115-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 1/24/70

Rotary Drilling Completed 2/5/70

LOCATION: Gleason "C" 2, NW NE NW Section 5-24S-21W,
Hodgeman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Run 13 Jts. 28# 8-5/8" surface casing set @ 265' KB. Cemented with 165 sacks
Completed 3:30 P.M. January 24, 1970. Circulated.

No oil string run. D & A Plugged 4 A.M. February 5, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

80	Top Soil - Sand		<u>C. F.S.</u>
265	Shale Shells		4355
592	Shale & Sand Streaks		4362
814	Red Bed & Shale		4385
840	Blaine		4403
905	Shale		4430
1095	Sand		4455
1445	Shale - Shells - Red Beds		4470
1462	Anhydrite		4505
1569	Shale - Shells		4585
2015	Shale		4620
2305	Shale & Lime		
2425	Lime - Shale		
2850	Lime		
3045	Lime & Shale		<u>S.L.M.</u>
3370	Shale & Lime		
3665	Lime & Shale	Strap	4081.73
3805	Shale & Lime	Board	4085.00
4035	Lime & Shale		3.27 Long
4620	Lime, RED		

Slope Test

- 2000
- 2500
- 3000
- 3500
- 4000
- 4500

RECEIVED
STATE COMMISSION
FEB 12 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
[Signature]
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.:

On this 10th day of February, 1970, before me the undersigned, a Notary Public, in and for

County of Sedgwick, State of Kansas, the said C. W. Sebitts, to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument, and acknowledged to me that he executed the same as his free and voluntary act and deed, and that he is an authorized officer and agent of such company, for the uses and purposes therein set forth.

Witness my hand and seal of office the day and year last above written.



January 19, 1973

Esther Lamone
Esther Lamone Notary Public