



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

5-26-72

RECEIVED  
STATE CORPORATION COMMISSION

MAY 26 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Justus of Jack Bowles has this

date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Jack Bowles

Complete Address: 401 Local Federal Bldg., Okla City, Okla.

Lease Name: Ryan Well No. 1

Location: C N/2 SW NW Sec. 25 Twp. 24 Rge. 23 <sup>XX</sup>~~(E)~~ (W)

County: Hodgeman Total Depth 4808' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Justus was instructed to plug the well as follows:


8 5/8" to 367' circulated w/ cement. Mud 4808' to 900'

Spot 100 Sacks cement 900' to 600' Mud 600' to 375'

Spot 30 sacks cement 375' to 275' Mud 275' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent