



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION
Wichita, Kansas

6-20-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clark of J. Bowles has this

date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Jack Bowles

Complete Address: 401 Local Federal Bldg., Okla. City, Oklahoma

Lease Name: Ryan Well No. 3

Location: C SW NE Sec. 25 Twp. 24 Rge. 23 ^{XX} (E) (W)

County: Hodgeman Total Depth 4880' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

8 5/8" to 365' circulated w/ cement. 5 1/2" to 4874' cemented

Top perforations 4651' Plug bottom w/ sand & 5 sacks cement.


Top of cement 4600' Mud 4600' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 365'

Spot 30 sacks cement 365' to 265' Mud 265' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent