



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Buck Ureuch of Helos Coaling Oulling has this date requested permission to plug the following described well:

Operator's Full Name: F. C. Hall

Complete Address: 6427 East Hellogg, Wichita, Kans. 67207

Lease Name: Cross Well No. #1-20

Location: 950' ESE - 1650' FEL - SE Sec. 20 Twp. 24 Rge. 17 (E) (W)

County: Edwards Total Depth: 4547 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Ureuch was instructed to plug the well as follows:

8 5/8" - 250 FT 50 cu 1/250st emt. → 4 1/2" set @ 4546 FT 1/150st emt.
Plug Back T.D. 4515 FT → Reop. Top. 4452 FT to 4456 FT
sand Bottom to 4400 FT 7 1/4st emt. Shot 9 times Recovered 2390 FT
Order 125st 20 Form 4 1/2 Gel - 3% Ca-Cl. → 25st Gel. → 6st shells. + 8 5/8" Plug.
Pump In 8 5/8" with Pump. touch. → Put In 15st Gel - 6st shells.
10st Gel. → Release Plug and 125st emt. → max Pressure 400 psi.

Very truly yours, By Allied Ltd

Marion Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1981

CONSERVATION DIVISION
Wichita, Kansas