

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name: Minnie C. Malin Well No. # 1

Location: C NW NE Sec. 27 Twp. 24 Rge. 17 (E) (W) W

County Edwards Total Depth 4405' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

259' of 8 5/8" surface pipe, cement circulated with 250 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement with

10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
Very truly yours,

6-28-65  
JUN 28 1965

Archie Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas