

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION5-19-64  
MAY 19 1964

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. F. L. Copeland of Western Petroleum Co., Inc has this  
 date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co., Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name: Bogerd Well No. # 1

Location: NE NE NE Sec. 10 Twp. 24 Rge. 18 (E) (W) W

County Edwards Total Depth 4840 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cement circulated. Fill hole  
with drilling mud to 275', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent