



15-047-21035-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

2 - May 1982

RECEIVED 5-6-82
STATE CORPORATION COMMISSION

MAY - 6 1982
CONSERVATION DIVISION
Wichita, Kansas
VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-047-21,035

Dear Sir:

Mr. Dean Calvin of White & Ellis Drilling Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Imperial Oil Co.

Complete Address: 720, 4th Financial Center, Wichita, Kansas

Lease Name: Wheaton Well No. 1-20

Location: 100' N. C. E/2 - SE Sec. 20 Twp. 24 Rge. 18 (E) (41)

County: Edwards Total Depth: 4590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Calvin was instructed to plug the well as follows:

They topped the anhydrite at 1000'. They cement circulated 593'
of 8 5/8" surface casing. 1st plug at 960' with 25 bbls of cement.
2nd plug 630' with 45 bbls of cement. 3rd plug 40' too' on
solid bridge with 10 bbls of cement. They circulated 10 bbls
of cement in rat hole. They pumped the cement through drill pipe
with hole full of heavy mud. The plugging was accomplished by
Sun Cementing. Put 5 bbls cement in water well.
Very truly yours,

Paul A. Luthi
Conservation Division Agent