

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

17 December 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-047-20977-0000

Dear Sir:

Mr. Dan Jones of White + Ellis Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Imperial Oil Co.

Complete Address: 720 Fourth Financial Center, Wichita, Kansas 67202

Lease Name: Cross Well No. 1-20

Location: C-NW-NW Sec. 20 Twp. 24 Rge. 18W (E) (W)

County: Edwards Total Depth: 4640'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Jones was instructed to plug the well as follows:

There is 596' of 8 3/8" surface casing cement circulated with 200 lbs light + 125 lbs common with 3% Jell + 3% c.c. The anhydrate is from 617' to 627'. 1st plug at 630' with 85 lbs cement, 2nd plug push rubber plug to 570' with 35 lbs cement on top of it. 2nd plug 40' to 0' on solid bridge with 10 lbs cement. Then pumped 5 lbs cement in rat hole + 2 lbs cement in water well. The plugging accomplished by with 2% Jell + 3% c.c.

Very truly yours,

12-22-81

Paul Luther
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1981
CONSERVATION DIVISION
Wichita, Kansas