

State of Kansas



15-047-00265-0000

FORM - CP-8  
Rev. 8-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-64  
NOV 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Web Hill of Mack Oil Company has this

date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: Moran Well No. # 1

Location: C SW SW Sec. 23 Twp. 24 Rge. 20 (E) (W) W

County Edwards Total Depth 4700 Oil Well     

Gas Well      Input Well      SWD Well      D & A X lost Hole     

Mr. Hill was instructed to plug the well as follows:

283' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 275', 1st cementing plug, bridge,  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat and mouse  
with 4 sacks.

Very truly yours,

*Archie Elving*