



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-6-64
JUL 6 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dean Glover of Slawson Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Glover guarantees payment of the plugging fee.

Operator's full Name: Donald Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name: Wagner "D" Well No. # 1

Location: C NE NW Sec. 21 Twp. 24 Rge. 20 (E) (W) W

County Edwards Total Depth 4685 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glover was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cemented with 225 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent