



15-047-00273-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

FEB 14 1964
2-14-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil of Kansas has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas Inc.

Complete Address: 780 4th National Bldg., Wichita, Kansas

Lease Name: Westphal Well No. # 1

Location: C SW SE Sec. 18 Twp. 24 Rge. 20 (E) (W) W

County Edwards Total Depth 4699 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated. Spot 25
sacks cement at 600', through drill pipe. Spot 20 sacks
cement at 240', through drill pipe. Fill hole with mud to
40', cementing plug, bridged with hulls, cemented with 10
sacks to base cellar. These orders were given by Hugh Scott.

Very truly yours,

Archie Elving
Conservation Division Agent