

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Sinclair Oil & Gas Co.

Complete Address: P. O. Box 521, Tulsa, Oklahoma

Lease Name: Kindsvater Well No. # 1

Location: C NE NW Sec. 28 Twp. 24 Rge. 19 (E) (W) W

County ~~Stafford~~ Edwards Total Depth 4619 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

295' of 8 5/8" surface pipe, cement circulated with 200
sacks. 4619' of 4 1/2" long string cemented with 150 sacks.
Perforation 4558' to 70'. Sand to 4540', cement with 3
sacks. Fill hole to 200' with mud, 19' rock bridge,
cement with 20 sacks. Fill hole to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
 Conservation Division Agent