



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

21 September 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-047-23932  
20932-0000

Dear Sir:

Mr. Dick Meade (Drilling Sup.) of Sterling Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: F. J. Holl

Complete Address: 6427 East Kellogg, Wichita Kans 67202

Lease Name: Cross Well No. 4-24

Location: 990' FNL-660' WL NE 1/4 Sec. 24 Twp. 24 Rge. 18W(E) (VA)

County: Edwards Total Depth: 4600'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Meade was instructed to plug the well as follows:

Elevation 2137 C.L. anhydrite 1186-1202. There is 256' of 8 5/8" surface casing cemented with 210 lbs 10/40 P<sub>2</sub>O<sub>2</sub>. Circulated hole & filled with mud. 1st plug 850' with 50 lbs <sup>cement</sup> 2nd plug 300' with 30 lbs cement. 3rd plug 40' to 0' with 10 lbs cement, 10 lbs in rat hole. Cement used was 50-50 P<sub>2</sub>O<sub>2</sub> mix 2% gel + 3% C.C. These instructions were given him by Mr. Gilbert J. Loman. Box 180 Holyroot Kans 67450. Haliburton did the cementing.

Very truly yours,

Paul Luthi  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1981

CONSERVATION DIVISION  
Wichita, Kansas