

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

6-1-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-047-21042

Dear Sir:

Mr. Jim Shruener of Sterling Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: F. G. HallComplete Address: 6427 East Kellog Wichita Kansas 67207Lease Name: Cross Well No. 5-24Location: 440' FSL-440' FEL-SE/4 Sec. 24 Twp. 24 Rge. 18 (E) (W)County: Edwards Total Depth: 4625'Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Shruener was instructed to plug the well as follows:

They cement circulated 253' of 8 7/8" surface casing. The anhydrite was taped at 1191'. 1st plug at 1080' with 40 sby of cement. 2nd plug at 320' with 50 sby of cement. 3rd plug on solid bridge at 40' to 0' with 10 sby of cement. Then circulated 10 sby of cement in rat hole. They put 5 sby of cement in water well. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Cementing.

Very truly yours,

Paul A. Luthie
Conservation Division Agent