

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-21042-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name F. S. Hall

Complete Address 6427 East Kellogg, Wichita, Kansas 67207

Lease Name Cross Well No. 5-24

Location 440' FSL-440' FEL of SE/4 Sec. 24 Twp. 24 Rge. 18 (East)(West)

County Edwards Total Depth 4625'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Co.

Address Box 129 Sterling Kans. 67579 License No. \_\_\_\_\_

Operation Completed: Hour: 3:30 P.M. Day: 2 Month: June Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

The anhydrite was topped at 1191'. 1st plug at 1080' with 40 Sbk of cement. 2nd plug at 320' with 50 Sbk of cement. 3rd plug on solid bridge at 40' to 0' with 10 Sbk of cement. Then they circulated 10 Sbk of cement in rat hole. The cement was pumped through drill pipe. Then they put 5 Sbk of cement in water well. The cement used was 50/50 paste with 2% gel + 3% C.C. The plugging was accomplished by Halliburton Cementing.

Amount of Surface Casing: 253' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

6-8-82

JUN - 8 1982

CONSERVATION DIVISION  
Wichita, Kansas JUN - 8 1982

Signed: \_\_\_\_\_  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 6-14-82

INV. NO. 419-10