

15-083-10068-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas

Lease Name Strecker "A" Well No. 3

Location C SW NW Sec. 9 Twp. 24 Rge. 21 (EA) (W)

County Hodgeman Total Depth 4677'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Southwest Casing Pulling

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 7:30PM Day 12 Month 5 Year 1966

The Above well was plugged as follows:

8 5/8" to 234' circulated w/ cement. 4 1/2" to 4675' cemented.

No Perforations Plug bottom w/ 75' of sand & 5 sacks cement.

Top of cement 4550' Mud 4550' to 285'

Plug & 40 sacks cement, 285' to 165' Mud 165' to 30'

Plug top w/ 10 sacks of cement 30' to 0. Welded Plate on 8 5/8".

Company Pump Pulled 2220' of 4 1/2" Casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Green  
Well Plugging Supervisor

DATE 5-16-66

INV. NO. 3218-W