

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Co.

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Gleason "C" Well No. 1

Location C N/2 NW NW Sec. 5 Twp. 21 Rge. 21 (E) (W)

County Hodgeman Total Depth 4665'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Russ Casing Pulling Co.

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 3:00PM Day 30 Month 6 Year 1970

The above well was plugged as follows:

8 5/8" to 260' circulated w/ cement. 5 1/2" to 4650' cemented.

Top perforations 4432' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4350' Mud 4350' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 260'

Spotted 30 sacks cement 260' to 160' Mud 160' to 40'

Plug, Huls ! 10 sacks cement 40' to 0'. Globe cementing Pump Truck.

Pulled 2698' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar J. Jones*
Well Plugging Supervisor

DATE 9/2/70

INV. NO. 2159-4