


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County, Sec. 34 Twp. 25 Rge. (E) 16 (W)  
Location as "NE/CNW&SW¼" or footage from lines C SE NW  
Lease Owner Santa Fe Pipe & Supply Company  
Lease Name Mayhew Well No. 3  
Office Address Box 562, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed November 13 19 62  
Application for plugging filed October 30 19 64  
Application for plugging approved November 2 19 64  
Plugging commenced November 7 19 64  
Plugging completed November 16 19 64  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	396	8 5/8"	396'	none
		0	4496	4 1/2	4496	3408.40

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 4450'. Set 10' rock bridge and dumped 3 sacks of cement.  
Pushed plug to 275'. Set 15' rock bridge. Mixed 4 sacks of cement and 5 lbs. of calcium chloride and dumped at 260'.  
Bailed hole down and dumped 21 sacks of cement. Filled hole with mud to 35', set 5' rock bridge and capped with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 7 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
Dean Wells (employee of owner) or (owner-or-operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells  
Ellinwood, Kansas

SUBSCRIBED AND SWORN to before me this 17 day of November, 19 64

J. J. Kader  
Notary Public.

My commission expires July 7, 1968

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas

**COPY**


15-047-10115-0000

Company- STATESWIDE OIL CORP.  
Farm- Mayhew No. 3

SEC. 34 T. 25 R. 16W  
C SE NW

Total Depth. 4500'  
Comm. 11-2-62 Comp. 11-13-62  
Shot or Treated.  
Contractor. Leben Dylg., Inc.  
Issued. 8-17-63

County Edwards  
KANSAS



CASINO:  
8 5/8" 396' cem w/275 ex.  
4 1/2" 4500'

Elevation. 2075' RB

Production. TEMP. ABDN.

Figures Indicate Bottom of Formations.

sand	40
sand & shale	389
red bed & shale	700
shale & red bed	1340
shale	2100
shale & lime	2230
lime	2480
lime & shale	2975
shale	3160
shale w/lime	3250
shale & lime	3510
lime & shale	3665
lime	3755
shale & lime	3870
lime & shale	3965
lime	4455
lime & shale	4500 RTD
Total Depth	

TOPS; LOG	
Heebner	3749
Toxonto	3770
Douglas	3788
Brown Lime	3890
Lansing	3908
Base Kansas City	4194
Cherokee Sand	4358
Shaley Conglomerate	4380
Mississippi	4400
Kinderhook Sand	4454

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 7 1965

CONSERVATION DIVISION  
Wichita, Kansas