


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Major Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County. Sec. 34 Twp. 35S Rge. (E) 16(W)

Location as "NE/CNW%SW%" or footage from lines C NW NW  
Lease Owner Leben Drilling Inc.  
Lease Name Mayhew Well No. 1  
Office Address Box 486, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed May 21 19 68  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced June 14 19 68  
Plugging completed June 24 19 68  
Reason for abandonment of well or producing formation depleted



If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4545 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	418'	8 5/8"	418'	none
		0	4540'	5 1/2"	4540'	3271.75

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand back from 4545' to 4400' and dumped 5 sacks cement.  
Set bridge at 390' and dumped 25 sacks cement. Set bridge at 40' to 30' and dumped 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1968

My commission expires July 7, 1968 [Signature] Notary Public.

DRILLER'S LOG

COMPANY: State Wide Oil Corporation  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: MAYHEW #1  
 LOCATION: NW NW Sec. 34-25S-16W  
 EDWARDS COUNTY, KANSAS  
 COMMENCED: 4-10-62  
 COMPLETED: 4-23-62

0	90	Sand
90	222	Sand & Shale
222	310	Sand & Shells
310	360	Sand & Shale
360	420	Shale & Shells
420	730	Shale & Redbed
730	1070	Redbed & Sand
1070	1100	Anhydrite
1100	1960	Shale & Shells
1960	2190	Shale
2190	2680	Lime
2680	2855	Lime & Shale
2855	2940	Shale & Lime
2940	3060	Lime
3060	3215	Shale & Lime
3215	3350	Lime
3350	3615	Lime & Shale
3615	3985	Shale & Lime
3985	4075	Lime & Shale
4075	4297	Lime
4297	4365	Shale & Lime
4365	4435	Lime
4435	4490	Chert & Shale
4490	4507	Shale & Chert
4507	4545	Lime & Chert
	<u>4545</u>	Rotary Total Depth - Set 5 1/2" Casing

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" Used surface casing @ 418'. Cemented with 275 sacks of Sunset cement by Sun.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mayhew #1, located NW NW of Section 34, Township 25 South, Range 16 West, Edwards County, Kansas as reflected by the files of the Leben Drilling, Inc.

*Byron Johnson*

Byron Johnson

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 26th day of April, 1962.

*Ulanda Nichols*

Ulanda Nichols

My Commission Expires:  
 April 1, 1963