


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County. Sec. 34 Twp. 25S Rge. (E) 16(W)
Location as "NE/CNW/SW" or footage from lines. C NE NW
Lease Owner Leben Drilling Inc.
Lease Name Mayhew Well No. 2
Office Address Box 486, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed May 21 1968
Application for plugging approved _____ 19____
Plugging commenced June 20 1968
Plugging completed June 24 1968
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	400'	8 5/8"	400'	none
		0	4456'	4 1/2"	4456'	1699.88

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back from 4460' to 4000' and dumped 5 sacks cement.
Pushed plug to 380', set 10' rock bridge and dumped 5 sacks cement over night. Dumped 20 sacks cement on bridge. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 19 68

My commission expires July 7, 1968 [Signature] Notary Public.

15-047-00130-0001

C. W. SMITH

petroleum geologist

232 Bonnie Bree - Wichita 8, Kansas - Murray 2-2571

May 6, 1962

Statewide Oil Corporation
8530 Wilshire Boulevard
Beverly Hills, California

Re: Stateswide No. 2 Mayhew
C NE NW 34-25S-16W
Edwards County, Kansas

Gentlemen:

The following is a geological report and electric log analysis on the above captioned well, which is a washdown of the old Smitherman No. 1 Mayhew "E", drilled in August, 1959, and abandoned as a dry hole. The well was not previously logged and, according to public reports, was not tested in any of the Mississippian, Conglomerate or Lansing formations.

When the Stateswide No. 1 Mayhew was completed for a Mississippian producer with Conglomerate production behind the pipe, it was recommended by the undersigned that this well be washed down and logged.

The following is a recap of the washdown and logging operations.

Elevation 2072 RB -- 2067 GL

Electric Log Formation Tops

Council Grove	2556	(- 484)
Topeka	3326	(-1254)
Heebner	3736	(-1664)
Toronto	3756	(-1684)
Douglas	3776	(-1704)
Brown Lime	3876	(-1804)
Lansing-Kansas City	3892	(-1820)
Base of Kansas City	4178	(-2106)
Fort Scott	4324	(-2252)
Cherokee	4344	(-2272)
Conglomerate Chert	4366	(-2294)
Mississippi	4380	(-2308)
Kinderhook Shale	4426	(-2354)
Kinderhook Sand	4446	(-2374)
Rotary Total Depth	4460	(-2388)

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1968
CONSERVATION DIVISION
Wichita, Kansas

DRILLING INFORMATION ON THE NO. 2 MAYHEW

Contractor: Leben Drilling, Inc.
Tool Pusher: Jack Ensminger
Geologist: C. W. Smith

Drillers: Whited
Hamilton
Saunders

Spud Date: 5-3-62
Surface Pipe: 8-5/8" @ 400'

Date of RTD: 5-5-62
Casing: 4 1/2" @ 4456'

5/2/62: Moved in rotary tools.
Drilled plug at 12:30 p.m.

5-3-62: 3010' at 7:30 a.m.

5-4-62: 4210' at 7:30 a.m.
4460' at 1:00 p.m.

Conditioned mud.
Made trip and strapped pipe.
Circulated to condition hole.

5-5-62: Ran Welox Radiation Guard Log.

Set 4 1/2" casing at 4456' with 1000 gallons of
Sun Latex cement.
Shoe Joint = 32.92'.
Zero Point = 5.26' above bradenhead.
Plug down at 8:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1968
CONSERVATION DIVISION
Wichita, Kansas