


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 34 Twp. 25S Rge. 16W NW/4
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

SW SW SW
Lease Owner Sterling Drilling Company
Lease Name Cudney "C" 3-34 Well No. 3-34
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above Section Plat

Date Well completed April 21, 1981
Application for plugging filed April 21, 1981
Application for plugging approved April 21, 1981
Plugging commenced 12:45 PM, April 21, 1981
Plugging completed 2:30 PM, April 21, 1981
Reason for abandonment of well or producing formation _____
Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	455'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud through open ended drill pipe;
50 sacks at 520'; 40 sacks at 450', Bridge,
1/2 sack hulls, plug and 10 sacks at 40';
10 sacks in rat hole.

4-23-81

RECEIVED
STATE CORPORATION COMMISSION


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,
STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1981.



Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My commission expires _____

15-047-20846-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - CUDNEY "C" 3-34
Located: SW SW SW, Section 34-25S-16W, Edwards County, Kansas.

OWNER: Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 13, 1981
COMPLETED: April 21, 1981

TOTAL DEPTH: 4560'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 459 Sand and Clay	Ran 11 joints 8 5/8", 28# used OD casing.
459 - 1060 Shale	444.04' pipe set at 455' K.B. Cemented
1060 - 1075 Anhydrite	with 400 sacks 60/40 Pozmix with 2% gel and
1075 - 1450 Shale and Lime Strs.	3% cc. Plug down at 12:30 AM, 4-14-81, by
1450 - 4500 Lime and Shale	Howco.
4500 - 4560 Lime	Plugged.

Deviation Surveys: 1° at 2183
1 1/4° at 4100'

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1981
4-23-81
CONSERVATION DIVISION
Wichita, Kansas